



TOWN OF JACKSON PLANNING & BUILDING DEPARTMENT

TRANSMITTAL MEMO

Town of Jackson

- Public Works/Engineering
- Building
- Title Company
- Town Attorney
- Police

Joint Town/County

- Parks and Recreation
- Pathways
- Housing Department

Teton County

- Planning Division

- Engineer
- Surveyor- *Nelson*
- Assessor
- Clerk and Recorder
- Road and Levee

State of Wyoming

- Teton Conservation
- WYDOT
- TC School District #1
- Game and Fish
- DEQ

Federal Agencies

- Army Corp of Engineers

Utility Providers

- Qwest
- Lower Valley Energy
- Bresnan Communications

Special Districts

- START
- Jackson Hole Fire/EMS
- Irrigation Company

Date: August 10, 2020

Item #: P20-152

Planner: Brendan Conboy

Phone: 733-0440 ext. 1302

Email: bconboy@jacksonwy.gov

Owner:

Smilie Times
PO Box 4932
Jackson, WY 83001

Applicant:

Greg Mason
PO Box 4659
Jackson, WY 83001

Please respond by: N/A

REQUESTS:

The applicant is submitting a request for a Grading Pre-Application for the property located at 385 E. Broadway Ave., legally known as, SO. 1/2, LOTS 5,6, BLK. 2, L.G. GILL SUBDIVISION.

For questions, please call Brian Lenz at 307-733-0440, x1410 or email to the address shown to the left. Thank you.

RESPONSE: For Departments not using Trak-it, please send responses via email to:
tstolte@jacksonwy.gov



PRE-APPLICATION CONFERENCE REQUEST (PAP)
Planning & Building Department

150 E Pearl Ave. | phone (307)733-0440
P.O. Box 1687 | www.townofjackson.com
Jackson, WY 83001

For Office Use Only

Fees Paid _____

Time & Date Received _____

Application # _____

Please note: Applications received after 3 PM will be processed the next business day.

APPLICABILITY. This application should be used when applying for a **Pre-application Conference**. The purpose of the pre-application conference is to identify the standards and procedures of these LDRs that would apply to a potential application prior to preparation of the final proposal and to identify the submittal requirements for the application.

For additional information go to www.townofjackson.com/204/Pre-Application

PROJECT.

Name/Description: _____

Physical Address: _____

Lot, Subdivision: _____

PIDN: _____

PROPERTY OWNER.

Name: _____

Phone: _____

Mailing Address: _____

ZIP: _____

E-mail: _____

APPLICANT/AGENT.

Name, Agency: _____

Phone: _____

Mailing Address: _____

ZIP: _____

E-mail: _____

DESIGNATED PRIMARY CONTACT.

Property Owner

Applicant/Agent

Please include Braden Olson and Dave Dufault with Nelson Engineering in the scheduling process to ensure that a time can be set for this project
bolson@nelsonengineering.net
ddufault@nelsonengineering.net

ENVIRONMENTAL PROFESSIONAL. For EA pre-application conferences, a qualified environmental consultant is required to attend the pre-application conference. Please see Subsection 8.2.2.C, Professional Preparation, of the Land Development Regulations, for more information on this requirement. Please provide contact information for the Environmental Consultant if different from Agent.

Name, Agency: _____ Phone: _____
Mailing Address: _____ ZIP: _____
E-mail: _____

TYPES OF PRE-APPLICATION NEEDED. Check all that apply; see Section 8.1.2 of the LDRs for a description of review process types.

Physical Development Permit
 Use Permit
 Development Option or Subdivision Permit
 Interpretations of the LDRs
 Amendments to the LDRs
 Relief from the LDRs
 Environmental Analysis

This pre-application conference is:
 Required
 Optional
 For an Environmental Analysis
 For grading

SUBMITTAL REQUIREMENTS. Please ensure all submittal requirements are included. The Planning Department will not hold or process incomplete applications. Provide **one electronic copy** (tstolte@jacksonwy.gov).

Have you attached the following?

Application Fee. Go to www.townofjackson.com/204/Pre-Application.com for the fees. **\$150.00 8-5-20**
 Notarized Letter of Authorization. A notarized letter of consent from the landowner is required if the applicant is not the owner, or if an agent is applying on behalf of the landowner. Please see the Letter of Authorization template at www.townofjackson.com/DocumentCenter/View/102/Town-Fee-Schedule-PDF.


Narrative Project Description. Please attach a short narrative description of the project that addresses:
 Existing property conditions (buildings, uses, natural resources, etc)
 Character and magnitude of proposed physical development or use
 Intended development options or subdivision proposal (if applicable)
 Proposed amendments to the LDRs (if applicable)

Conceptual Site Plan. For pre-application conferences for physical development, use or development option permits, a conceptual site plan is required. For pre-application conferences for interpretations of the LDRs, amendments to the LDRs, or relief from the LDRs, a site plan may or may not be necessary. Contact the Planning Department for assistance. If required, please attach a conceptual site plan that depicts:
 Property boundaries
 Existing and proposed physical development and the location of any uses not requiring physical development
 Proposed parcel or lot lines (if applicable)
 Locations of any natural resources, access, utilities, etc that may be discussed during the pre-application conference

Grading Information (REQUIRED ONLY FOR GRADING PRE-APPS). Please include a site survey with topography at 2-foot contour intervals and indicate any areas with slopes greater than 25% (or 30% if in the NC Zoning District), as well as proposed finished grade. If any areas of steep slopes are man-made, please identify these areas on the site plan.

Other Pertinent Information. Attach any additional information that may help Staff in preparing for the pre-app or identifying possible key issues.

Under penalty of perjury, I hereby certify that I have read this application and state that, to the best of my knowledge, all information submitted in this request is true and correct. I agree to comply with all county and state laws relating to the subject matter of this application, and hereby authorize representatives of Teton County to enter upon the above-mentioned property during normal business hours, after making a reasonable effort to contact the owner/applicant prior to entering.


Signature of Owner or Authorized Applicant/Agent

Date

Name Printed

Title

LETTER OF AUTHORIZATION

Melissa Larsen, "Owner" whose address is: 385 E.

Broadway

(NAME OF ALL INDIVIDUALS OR ENTITY OWNING THE PROPERTY)

Melissa Larsen, as the owner of property

more specifically legally described as: 385 EAST BROADWAY

SOUTH 1/2 LOTS 5,6 BLK 2, L.G., GILL SUBDIVISION

(If too lengthy, attach description)

HEREBY AUTHORIZES KRIKOR ARCHITECTURE, LLC GREGORY MASON as

agent to represent and act for Owner in making application for and receiving and accepting on Owners behalf, any permits or other action by the Town of Jackson, or the Town of Jackson Planning, Building, Engineering and/or Environmental Health Departments relating to the modification, development, planning or replatting, improvement, use or occupancy of land in the Town of Jackson. Owner agrees that Owner is or shall be deemed conclusively to be fully aware of and to have authorized and/or made any and all representations or promises contained in said application or any Owner information in support thereof, and shall be deemed to be aware of and to have authorized any subsequent revisions, corrections or modifications to such materials. Owner acknowledges and agrees that Owner shall be bound and shall abide by the written terms or conditions of issuance of any such named representative, whether actually delivered to Owner or not. Owner agrees that no modification, development, platting or replatting, improvement, occupancy or use of any structure or land involved in the application shall take place until approved by the appropriate official of the Town of Jackson, in accordance with applicable codes and regulations. Owner agrees to pay any fines and be liable for any other penalties arising out of the failure to comply with the terms of any permit or arising out of any violation of the applicable laws, codes or regulations applicable to the action sought to be permitted by the application authorized herein.

Under penalty of perjury, the undersigned swears that the foregoing is true and, if signing on behalf of a corporation, partnership, limited liability company or other entity, the undersigned swears that this authorization is given with the appropriate approval of such entity, if required.

OWNER:

Melissa Larsen

(SIGNATURE) (SIGNATURE OF CO-OWNER)

Title: Melissa Larsen - Officer - Smilie Times, Inc.

(if signed by officer, partner or member of corporation, LLC (secretary or corporate owner) partnership or other non-individual Owner)

STATE OF WYOMING

)

)SS.

COUNTY OF TETON

)


The foregoing instrument was acknowledged before me by Melissa Larsen this 10th day of August, 2020.

WITNESS my hand and official seal.

Melisa Molina

(Notary Public)

My commission expires:



7 August 2020

Town of Jackson
Planning & Building Department-Planning Division
150 E. Pearl Ave.
PO Box 1687
Jackson, WY 83001

To Whom it May Concern,


The Attached PAP is for the demolition of existing structures and new residential construction located at 385 E Broadway Ave. & 370 E Deloney Ave in Jackson, WY. In accordance with the existing site plan attached, there is an existing residence with associated parking and utilities. Proposed development includes demolition of the existing structures and construction of a new residence, access, and garage with associated utilities and access easement. Proposed development is described on sheets C2.0-C4.1 attached. Please don't hesitate to contact us with project inquiries.

Sincerely,

A handwritten signature in black ink, appearing to read "Gregory Mason".

Gregory Mason, AIA, LEED AP
KRIKOR Architecture

Office: 307.413.6874
Email: krikorarch@gmail.com



LEGEND

	= BOUNDARY
	= SETBACK LINE
	= CENTERLINE OF ROAD
	= CURB LINE
	= EDGE OF GRAVEL
	= FENCE LINE- WOOD
	= FENCE LINE - CHAIN LINK
	= RAILROAD TIES
	= BUILDING LINE
	= BURIED POWER LINE
	= BURIED TELEPHONE LINE
	= BURIED CABLE TV LINE
	= GAS LINE
	= SANITARY SEWER LINE
	= SHRUB LINE
	= SANITARY SEWER SERVICE PER TOJ GIS
	= STORM SEWER LINE PER TOJ GIS
	= WATER LINE PER TOJ GIS
	= WATER SERVICE LINE PER TOJ GIS
	= DECK - WOOD
	= LANDSCAPING
	= STONE PATHWAY/PATIO
	= CONCRETE WALKWAY
	= GRAVEL
	= PAVEMENT
	= BUILDING COLUMN
	= BOULDER
	= CABLE TV PEDESTAL
	= CURB STOP
	= ELECTRIC METER
	= GAS METER
	= IRRIGATION BOX
	= IRRIGATION CONTROLLER VALVE
	= POST
	= POWER SOCKET
	= SIGN
	= SANITARY SEWER CLEANOUT PER OWNERS
	= SANITARY SEWER MH
	= STORM SEWER MH
*	= SPRINKLER
	= TELEPHONE PEDESTAL
	= WATER SPICKET
	= WATER VALVE
	= ASPEN TREE
	= BUSH
	= DECIDUOUS TREE W/ TRUNK DIA.
	= FIR TREE W/ TRUNK DIA.
	= WILLOW TREE W TRUNK DIA.
	= FOUND NELSON REBAR AND CAP
	= FOUND REBAR AND CAP
	= FOUND T-STAKE
	= FOUND PIPE

DEMOLITION NOTES

1. DEMOLITION ACTIVITIES SHALL OCCUR DURING SUMMER/FALL 2020.

2. COMPLY WITH APPLICABLE SITE CONSTRUCTION NOTES ON SHEET C2.0.

3. DEMOLITION WORK SHALL COMPLY WITH ALL APPLICABLE REQUIREMENTS OF THE APPROVED PERMIT AND IBC REGULATIONS. SALVAGE EXISTING WATER METER IN ACCORDANCE WITH NOTE 7 BELOW.

4. CONTRACTOR SHALL VERIFY LOCATIONS OF EXISTING UTILITIES BY CONTACTING UTILITY PROVIDERS, CAMERA INSPECTION, LOCATING DEVISE/SERVICE, OR EXPLORATORY EXCAVATION.

5. CONTRACTOR SHALL OBTAIN RIGHT-OF-WAY PERMIT FROM THE TOWN OF JACKSON FOR WORK COMPLETED IN THE PUBLIC RIGHT-OF-WAY.


6. WATER AND SEWER UTILITY LOCATIONS WERE OBTAINED FROM TETON COUNTY GIS AND ARE APPROXIMATE. CONTRACTOR SHALL VERIFY LOCATION AND CAP NEAR PROPERTY LINE OR AT MAIN PER PLANS.

7. CONTRACTOR SHALL CAP EXISTING WATER SERVICE AT THE EXISTING CURB STOP AND MARK FOR FUTURE RE-CONNECTION IN ACCORDANCE WITH THE UTILITY PLAN FOR THE FUTURE DEVELOPMENT. EXISTING WATER METER MAY BE SALVAGED AND REUSED PENDING THE CONDITION; METER READING (UPON REMOVAL) SHALL BE RECORDED AND CONDITION ASSESSMENT SHALL BE COMPLETED BY TOJ PUBLIC WORKS.

8. INSTALL EROSION CONTROL MEASURES IN ACCORDANCE WITH NOTE 7, SHEET C2.0.

9. CONSTRUCT TRACK PAD (IF REQUIRED) IN ACCORDANCE WITH TOWN STANDARD DETAIL ST-119/C1.1 TO PREVENT TRACK-OUT OF SOILS ONTO PUBLIC STREETS.

10. CONTRACTOR SHALL CAP EXISTING SEWER SERVICE AT THE PROPERTY BOUNDARY AND MARK FOR FUTURE RE-CONNECTION IN ACCORDANCE WITH THE UTILITY PLAN FOR FUTURE DEVELOPMENT.




NOTES:

1. PLACE CONSTRUCTION GEOTEXTILE FOR SOIL STABILIZATION UNDER THE CRUSHED ROCK FROM THE EDGE OF THE EXISTING ROADWAY TO THE RADIUS RETURNS, OR AS DIRECTED BY PUBLIC WORKS.
2. ENTRANCE SHALL BE REMOVED AND RECONSTRUCTED AS REQUIRED TO PREVENT EXCESS TRACKING OF MATERIALS ONTO RIGHT-OF-WAY, OR WHEN DIRECTED BY THE TOWN PUBLIC WORKS DEPARTMENT.



ST-119 STABILIZED CONSTRUCTION ENTRANCE

ST-119 DATE: 12/5/12 SCALE: NTS



SITE CONSTRUCTION NOTES & SPECIFICATIONS

CAUTION: UNDERGROUND UTILITY LOCATIONS ARE NOT GUARANTEED, NOR IS THERE ANY GUARANTEE THAT ALL EXISTING UTILITIES (WHETHER FUNCTIONAL OR ABANDONED) WITHIN THE PROJECT AREA ARE SHOWN ON THESE CONSTRUCTION DRAWINGS. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL UNDERGROUND UTILITIES BEFORE STARTING WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGE RESULTING FROM CONTRACTORS WORK.

1. ALL SITE WORK SHALL BE DONE IN ACCORDANCE WITH WYOMING PUBLIC WORKS STANDARD SPECIFICATIONS (WPWSS) 2015 EDITION AND THESE PLANS.
2. CONTRACTOR REQUIRED TO MEET WYOMING DEPARTMENT OF ENVIRONMENTAL QUALITY'S STORMWATER PERMIT REQUIREMENTS.
3. IT IS RECOMMENDED THAT THE CONTRACTOR EMPLOY A SURVEYOR TO PROVIDE STAKING FOR LOCATIONS OF FOUNDATIONS, UTILITIES, DRIVEWAY, AND FOR GRADING WORK.
4. STRIPPED MATERIAL SHALL BE STOCKPILED AT STOCKPILE AREAS SHOWN ON PLAN, CUT MATERIAL WILL BE PLACED DIRECTLY INTO FILL AREAS OR STOCKPILED. SEE SHEET C4.0 FOR STAGING AND STOCKPILING LOCATIONS.
5. TOPSOIL SHALL BE STOCKPILED SEPARATELY & REUSED TO COVER FINISH AREAS. IMPORT ADDITIONAL WEED-FREE TOPSOIL IF NECESSARY TO COVER ALL DISTURBED AREAS NOT RECEIVING SURFACING. LEAVE SUBGRADE DOWN 4-6" TO RECEIVE TOPSOIL IN LANDSCAPE AREAS.
6. NEW DRIVEWAY, SIDEWALK, CURB AND GUTTER CONSTRUCTION SHALL CONFORM TO TOJ AND ADA STANDARDS. REPLACEMENT MATERIALS SHALL MATCH EXISTING. EXISTING SIDEWALKS SHALL BE MAINTAINED AND PROTECTED.
7. IN ACCORDANCE WITH C4.0, INSTALL EROSION CONTROL MEASURES PRIOR TO COMMENCING WITH LAND DISTURBING ACTIVITIES AND MAINTAIN THE DEVICES DURING CONSTRUCTION. IF NECESSARY THE CONTRACTOR SHOULD INSTALL AND MAINTAIN ADDITIONAL EROSION CONTROL MEASURES TO ENSURE THE SITE IS STABILIZED DURING CONSTRUCTION.
8. REVEGETATION SHALL BE NATIVE SEED AND SOD AND SHALL BE IRRIGATED BY OWNER WHEN NECESSARY.
9. CONTRACTOR MUST HAVE A WEED CONTROL PLAN PREPARED BY TETON COUNTY WEED AND PEST OR OTHER WEED SPECIALIST AND IMPLEMENT THE PLAN THROUGHOUT CONSTRUCTION. SEE NOTES THIS SHEET FOR WEED MANAGEMENT REQUIREMENTS.
10. LAND DISTURBING ACTIVITIES SHALL OCCUR FROM FALL 2020 THROUGH FALL 2022.
11. CONTRACTOR SHALL COORDINATE THE INSTALLATION OF WIRE UTILITY SERVICES WITH UTILITY PROVIDERS AND ARRANGE INSTALLATION AND SERVICE CONTRACTS.
12. IF A GEOTECHNICAL REPORT WAS COMPLETED, CONTRACTOR SHALL FOLLOW RECOMMENDATIONS FOR FOUNDATION SOILS PREPARATION, FOUNDATION DRAIN PLACEMENT, FOUNDATION BACKFILL, DRIVEWAY CONSTRUCTION, AND OTHER SOIL PREPARATION FOR SLABS AND UTILITIES.
13. LANDSCAPING: ONE (1) PLANT UNIT IS REQUIRED; SEE LANDSCAPING PLANS. PER TOJ INSTALL BACKFLOW PREVENTION (REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTER) ON IRRIGATION SYSTEMS CONNECTING TO PUBLIC WATER SUPPLY.
14. CONTRACTOR SHALL COMPLY WITH THE FOLLOWING CONSTRUCTION MANAGEMENT REQUIREMENTS:
 - A. CONSTRUCTION PARKING AND STAGING SHALL OCCUR ALONG THE DRIVEWAY, WITHIN THE STAGING AREA, AND AT THE LOT FRONTEAGE. STAGING W/IN PUBLIC RIGHT-OF-WAYS IS PROHIBITED W/OUT AN ENCROACHMENT PERMIT.
 - B. STAGE MATERIALS AND EQUIPMENT WITHIN THE LOT BOUNDARY AND IN ACCORDANCE WITH SHEET C4.0. NO STAGING WITHIN PUBLIC RIGHT-OF-WAY IS ALLOWED.
 - C. TRACK-OUT OF DEBRIS ON PUBLIC ROADS IS PROHIBITED. PLACE GRAVEL SURFACING. TO MINIMIZE MUD ISSUES DURING CONSTRUCTION IN ACCORDANCE WITH ST-119/C1.1.
 - D. INSTALL CONSTRUCTION FENCING ALONG LIMITS OF DISTURBANCE TO CONTAIN CONSTRUCTION ACTIVITIES PER SHEET C4.0.
 - E. LOCATE AND PROVIDE TEMPORARY CONSTRUCTION FACILITIES INCLUDING TRAILERS, TOILETS, DUMPSTERS AND LOCATIONS FOR CONCRETE WASHOUT W/IN THE LOT BOUNDARY.
 - F. DUST CONTROL MUST BE ACCOMPLISHED BY WATERING STOCKPILES AND DRY SOILS.
15. FINAL GRADING INSPECTION: PER TOJ, CONTRACTOR/OWNER SHALL ARRANGE FOR GRADING INSPECTION AND FINAL APPROVAL BY THE DESIGN ENGINEER FOR PLAN-LEVEL GEC's
16. NEW BUILDING CONSTRUCTION SHALL BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE CODES INCLUDING, BUT NOT LIMITED TO THE MOST CURRENT EDITIONS OF THE INTERNATIONAL FIRE CODE (IFC), NATIONAL FIRE PROTECTION ASSOCIATION (NFPA), INTERNATIONAL RESIDENTIAL CODE (IRC), THE NATIONAL ELECTRIC CODE (NEC) AND INTERNATIONAL BUILDING CODE (IBC).

TETON COUNTY WEED AND PEST MANAGEMENT STRATEGIES

PRE-CONSTRUCTION MANAGEMENT STRATEGIES TO BE PERFORMED BY CONTRACTOR:

1. PRIOR TO CONSTRUCTION, CONTRACTOR SHALL CONTACT THE TETON COUNTY WEED & PEST, OR OTHER QUALIFIED PROFESSIONAL, TO CONDUCT A SITE SPECIFIC INVENTORY OF INVASIVE SPECIES AND CREATE A SPECIES SPECIFIC MANAGEMENT PLAN IN ACCORDANCE WITH TETON COUNTY LDR 5.7.2.


ACTIVE CONSTRUCTION MANAGEMENT STRATEGIES TO BE PERFORMED BY CONTRACTORS

1. ALL CONSTRUCTION EQUIPMENT TO BE CLEANED PRIOR TO ENTERING THE SITE.
2. SOIL STOCKPILES TO BE ROUTINELY CHECKED AND TREATED FOR INVASIVE SPECIES.
3. DISTURBANCE OUTSIDE OF THE CONSTRUCTION ZONE AND IN AREAS WHERE INVASIVE SPECIES ARE PRESENT SHALL BE MINIMIZED.
4. ALL AREAS OUTSIDE OF THE CONSTRUCTION ZONE SHALL BE KEPT ON ACTIVE MANAGEMENT USING THE CONTROL METHODS PRESCRIBED IN THE SPECIES SPECIFIC MANAGEMENT PLAN CREATED PRIOR TO CONSTRUCTION. THIS AREA SHALL BE MONITORED AND TREATED AT LEAST TWICE EACH GROWING SEASON.

POST-CONSTRUCTION MANAGEMENT STRATEGIES TO BE PERFORMED BY CONTRACTOR:

1. RE-VEGETATION TO OCCUR IMMEDIATELY AFTER CONSTRUCTION IS COMPLETE TO PREVENT THE ESTABLISHMENT OF INVASIVE SPECIES IN DISTURBED AREAS.
2. NURSERY STOCK SHALL BE IN ACCORDANCE WITH W.S. 11-9-101 – 109 (WYOMING NURSERY STOCK LAW), ACCCOMPANIED BY A VALID HEALTH CERTIFICATE, AND ACQUIRED THROUGH A DEALER LICENSED BY THE WYOMING DEPARTMENT OF AGRICULTURE. SEEDS SHALL BE IN ACCORDANCE WITH W.S. 11-12-101 – 125 (WYOMING SEED LAW), CERTIFIED WEED FREE, AND ACQUIRED THROUGH A DEALER LICENSED BY THE WYOMING DEPARTMENT OF AGRICULTURE.
3. CERTIFIED WEED FREE STRAW, GRAVEL, AND SOIL SHALL BE UTILIZED WHERE POSSIBLE.
4. TCWP TO BE CONTACTED TO CREATE A POST-CONSTRUCTION INVENTORY.


NELSON ENGINEERING P.O. BOX 1599, JACKSON WYOMING (307) 733-2087		FINAL SITE PLAN DRAWING TITLE 20-180-02	DATE 8/7/2020 SURVEYED DK ENGINEERED BO DRAWN BJG CHECKED DD APPROVED REV.
JOB TITLE LARSEN RESIDENCE 200 E 3855 E. BROADWAY & 370 E DELONEY JACKSON, WY			



UTILITY NOTES

SPECIAL PROVISIONS TO WPWSS (2015) – UTILITIES

- WATER SERVICE PIPE SHALL BE SDR11 POLYETHYLENE.
- WATERLINE SHALL BE BURIED WITH A MINIMUM OF SIX FEET OF COVER.
- GRAVITY SEWER PIPE SHALL BE 4"Ø ASTM D2665 SCH40 PVC.
- MINIMUM SEWER PIPE GRADE SHALL BE 2%, UNLESS OTHERWISE NOTED.
- INSULATE ALL WATER AND SEWER PIPES WITH LESS THAN 6' OF BURROWING.



NOTES:

1. WHEN ELECTRICAL CONDUCTORS CROSS OVER OR UNDER WATER AND/OR SEWER PIPES THERE SHALL BE A MINIMUM OF 12" VERTICAL SEPARATION. IN ADDITION, THE ELECTRICAL CONDUCTORS SHALL BE PROTECTED WITH NOT LESS THAN 48" OF SUITABLE PVC OR RIGID STEEL CONDUIT WITH NO LESS THAN 24" ON EITHER SIDE OF THE CROSSING.
2. CONSUMER INSTALLED CONDUIT MUST BE INSPECTED PRIOR TO BACKFILLING. IF NOT INSPECTED, TRENCH MAY BE REJECTED.
3. ALL TRENCHES ARE TO BE INSPECTED PRIOR TO BACKFILLING.
4. 18" SEPARATION MUST BE OBTAINED BETWEEN PE GAS PIPE AND POWER CABLE OR TRENCH WILL BE REJECTED.
5. BEDDING AND SHADING MATERIAL MUST BE SMOOTH, FREE OF ROCKS, AND MUST BE ABLE TO SIFT THROUGH A 1/4" SCREEN (SAND RECOMMENDED).

1 UTILITY TRENCH DETAILS

SCALE: N




W-103 SERVICE CONNECTION THAW WIRE
C3.0 DETAIL 1 OF 2

W-103 DATE: 12/30/

SCALE: NTS



NOTES:



NEILSON ENGINEERING

F

DRAWING NO		JOB TITLE	DRAWING TITLE
20-1800-02	3.0	LARSEN RESIDENCE	UTILITY PLAN
JOB NO		335 E. BROADWAY & 370 E DELONEY	
		JACKSON, WY	
		P.O. BOX 1599, JACKSON WYOMING (307) 733-2087	
		DATE 8/7/2020	REV.
		SURVEYED ENGINEERED	DK BO
		DRAWN	BJG
		CHECKED	DD
		REVISION	



DRAWING NO	JOB TITLE	DRAWING TITLE	REV.
C3.1	LARSEN RESIDENCE	385 E. BROADWAY & 370 E DELONEY	DK
20-180-02	JACKSON, WY		BO
			BIG
			DD
			APPROVED

NELSON
ENGINEERING

P.O. BOX 1599, JACKSON, WYOMING (307) 733-2087

